

**DNIT FOR THE CONSTRUCTION OF CATTLE SHED
200'X30' AT VILLAGE SUKHE MAJRA BLOCK
NURPURBEDI**

Sr.No	CSR	Description of Item	Unit	Qty	Rate	
1	6.6	Earth work in excavation in foundations, trenches etc. in all kinds of soil where pick jumper work is not involved and not exceeding 2.0 metres depth including dressing of bottom and sides of trenches, stacking the excavated soil clear from the edge of excavation.	cum	143.83	72.91	Rupees SeventyTwo And Paise NinetyOne Only
2	10.8b	Cement concrete 1:6:12 with 40 mm gauge stone ballast.	cum	12.15	1586.56	Rupees One Thousand Five Hundred EightySix And Paise FiftySix Only
3	10.15	Reinforced cement concrete M-20 mechanically batch mixed using batch type concrete mixer as per I S :1791 and vibrated by needle vibrator but excluding steel reinforcement centring shuttering in foundation and plinth.	cum	27.4	3349.8	Rupees Three Thousand Three Hundred FortyNine And Paise Eighty Only
4	18.18	Cold twisted deformed (Ribbed/ Tor Steel Bar) Bars Fe 500 grade as per IS 1786-1985, for R.C.C works, where not including in the complete rate of RCC	qtl	17.17	5202.76	Rupees Five Thousand Two Hundred Two And Paise SeventySix Only
5	18.15	Bolts and nuts of all sizes and length required.	Kg	239.81	60	Rupees Sixty Only
6	9.1	shuttering for faces of concrete for foundation and foundation beam	sqm	84.38	128.99	Rupees One Hundred TwentyEight And Paise NinetyNine Only
7	9.4	Centring and shuttering for columns (Square or rectangular or poly gonal in plain)	sqm	51.63	197.2	Rupees One Hundred NinetySeven And Paise Twenty Only
8	10.6 b	Cement Concrete 1:8:16 with 40mm gauge stone aggregate.	sqm	4.48	1432.15	Rupees One Thousand Four Hundred ThirtyTwo And Paise Fifteen Only
9	18.1 b	Steel work, fixed independently without connecting plates, including cutting, hoisting and fixing in position Providing and fixing MS plats	Qtl	6.96	5000.47	Rupees Five Thousand And Paise FourtySeven Only

10	18.1 A	Steel work, fixed independently without connecting plates, including cutting, hoisting and fixing in position Providing and fixing MS Round pipe	Qtl	16.88	5197.08	Rupees Five Thousand One Hundred NinetySeven And Paise Eight Only
11	18.3 a	Structural steel work in angles, tees and flats, riveted or welded including cutting fixing all gusset plates, bolts, nuts, rivets, welding rod, etc. with hoisting and erecting in position	qtl	81.7	6662.04	Rupees Six Thousand Six Hundred SixtyTwo And Paise Four Only
12	N.S	Providing and Fixing GI sheets 0.5 mm thick	sft	7400	AAR	0
13	18.4	Wrought iron and mild steel ladders, framed grills, grating etc. with ends of bars, riveted or welded or forged, framed indow guards, barred iron doors, stair case, iron railing including cost of bolts and nuts or screws or elding rod, complete fixed in position.	Qtl	2.57	7134.98	Rupees Seven Thousand One Hundred ThirtyFour And Paise NinetyEight Only
14	16.21+16.22	Painting two coats including priming coat with ready mixed paint for metallic surfaces in all shades on steel or iron work	sqm	435.81	51.54	Rupees FiftyOne And Paise FiftyFour Only
15	14.18	Dry brick on edge paving sand grouted over 50mm thick earth and mud plaster.	Sqm	503	238.4	Rupees Two Hundred ThirtyEight And Paise Fourty Only
NOTE:-		A C Slip No 11				
		D/d Rate of cement @ 50 Rs/bag				
		D/d of Rate mild steel @ 847 Rs /Qtl				
		D/d Rate structural steel including horizontal members, braces, vertical members, purlins etc, for truss @ 940.27 Rs/Qtl				
		D/d Rate tor Grill @ 895 Rs/Qtl				
		D/d Rate tor Cold twisted deformed FE 500 @ 933 Rs/Qtl				